PROJECT ID:	ARBOR TERRACE AT 6915 PEACHTREE DUNWOODY ROAD SANDY SPRINGS GA 30328	CLIENT'S INFORMATION:	
		CONTACT:	
		E-MAIL ADDRESS:	
SCOPE:	CMU, BRICKS, MASONRY, EIFS, FLASHING & TRIM	PHONE NUMBER:	
		Date:	04/19/24

ITEM #	DWG. #	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL COST	TRADE COST
		GENERAL REQUIREMENTS					
1		Supervision	1	LS	$0	$0	
2		Permits	1	LS	$0	$0	
3		Final Clean-up	1	LS	$0	$0	
4		Mobilization Costs	1	LS	$0	$0	
5		Project Overheads	1	LS	$0	$0	
6		Bonds	1	LS	$0	$0	
7		Temporary Control & Facilities	1	LS	$0	$0	
8		Scaffolding	1	SF	$0	$0	
		Subtotal (General Requirements)					**$0**
		DIVISION 04- MASONRY					
		CONCRETE MASONRY UNIT					
		STAIRS					
9	A701-A702	8" Thick CMU Wall Reinforcement: #4 Vert Rebar @ 16" O.C # 4 Vertical Dowel Bar @ 16" O.C (2) #9 Wire Horiz Ladder Style Joint Reinforcement @ 16" O.C S7.1	11563	SF	$0	$0	
13		8"x16" Bond Beam Lintels Reinforcement: 2#5 Cont Top Rebar 2#5 Cont Bottom Rebar S8.6	55	FT	$0	$0	
10		8"x8" Bond Beam Reinforcement: 2#4 Cont Rebar S8.4	211	FT	$0	$0	
11		8"x16" Bond Beam Reinforcement: 2#4 Cont Rebar S8.4	481	FT	$0	$0	
		Subtotal (Masonry)					**$0**
		DIVISION 09- FINISHES					
		EXTERIOR FINISHING					
		EXTERIOR FINISHING BUILDING					
12		Stone STN-01 MFR: CORONADO STYLE: ELEMENT LEDGESTONE COLOR: NORTHLAND	4349	SF	$0	$0	
13	A301-A061	Stone Sill CS1 MFR: CORONADO STYLE: 900 Series Sill Size: 2-1/2"x2-1/2"x24" COLOR: #2 Grey	660	FT	$0	$0	
14		Stone Corner STN03 MFR: CORONADO STYLE: Smooth Limestone Size: 6" Corners COLOR: NORTHLAND	617	FT	$0	$0	
15	A062	3" Thick Cast Stone Cap Width 10"	77.09	FT	$0	$0	
		Subtotal (Finishes)					**$0**

SUBTOTAL		**$0.00**
OVERHEAD & PROFIT	**20%**	**$0.00**
INSURANCE	**3%**	**$0.00**
CONTINGENCY	**7%**	**$0.00**
TOTAL BASE BID		**$0.00**

DYNAMIC ESTIMATION INC.