

PROJECT ID: Cherokee Country Traffic, K9 & Coroner Facility

CONTACT:

E-MAIL ADDRESS:

PHONE NUMBER:

Date: 08/17/22

SCOPE: ROOFING

ITEM #	DWG. #	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL COST	TRADE COST
GENERAL REQUIREMENTS							
1		Supervision	1	LS	\$0	\$0	
2		Permits	1	LS	\$0	\$0	
3		Final Clean-up	1	LS	\$0	\$0	
4		Mobilization Costs	1	LS	\$0	\$0	
5		Project Overheads	1	LS	\$0	\$0	
6		Bonds	1	LS	\$0	\$0	
7		Temporary Control & Facilities	1	LS	\$0	\$0	
		Subtotal (General Requirements)					\$0
DIVISION 07- THERMAL & MOISTURE PROTECTION							
		Building - B					
		Roof					
		Mian-Roofing					
8		60 MIL TPO Roof Membrane	5874	SF	\$0	\$0	
9		R25 Min. Roof Insulation	5022	SF	\$0	\$0	
10		Cover Board As Req. by Roof System	5022	SF	\$0	\$0	
11		Metal Deck	5022	SF	\$0	\$0	
12		Walkway Protection Membrane	333	SF	\$0	\$0	
		Canopy Roof					
13		Sloped Integral Gutter	38	LF	\$0	\$0	
14		1-1/2" Metal Decking	287	SF	\$0	\$0	
15		Metal Fascia	111	LF	\$0	\$0	
16		Downspout	20	LF	\$0	\$0	
		Misc.					
17		PT Wood Blocking As Req. By Roof System	627	LF	\$0	\$0	
18		Sealant & Backer Rod	209	LF	\$0	\$0	
19		Pre-finished Metal Flashing	209	LF	\$0	\$0	
20		24x24 Access Hatch With Required Flashing	1	EA	\$0	\$0	
21		Access Ladder	1	EA	\$0	\$0	
22		Flashing @ Condenser/HVAC Equipment Curb	67	LF	\$0	\$0	
23		Flashing @ VTR	2	EA	\$0	\$0	
24		Pre-finished Metal Gutter	106	LF	\$0	\$0	
25		Fascia Board	213	LF	\$0	\$0	
26		Downspout	100	LF	\$0	\$0	
27		4'-6"x17'-0" Pre-engineered Canopy W/ Hanger Rods - BOD: Mapes, 18" Edge Channel	1	EA	\$0	\$0	
28		5'-0"x20'-0" Pre-engineered Canopy W/ Hanger Rods - BOD: Mapes, 18" Edge Channel	1	EA	\$0	\$0	
29		5'-0"x32'-6" Pre-engineered Canopy W/ Hanger Rods - BOD: Mapes, 18" Edge Channel	1	EA	\$0	\$0	
30		Pre-finished Metal Coping	213	LF	\$0	\$0	
31		Counterflashing @ parapet	213	LF	\$0	\$0	
		Building - A					
		Roof					
		Roofing					
32		60 MIL TPO Roof Membrane	9860	SF	\$0	\$0	
33		R25 Min. Roof Insulation	8452	SF	\$0	\$0	
34		Cover Board As Req. by Roof System	8452	SF	\$0	\$0	
35		Metal Deck	8452	SF	\$0	\$0	
36		Walkway Protection Membrane	408	SF	\$0	\$0	
		Misc.					
37		Pre-finished Metal Gutter	130	LF	\$0	\$0	
38		Downspout	96	LF	\$0	\$0	
39		PT Wood Blocking As Req. By Roof System	1056	LF	\$0	\$0	
40		Sealant & Backer Rod	352	LF	\$0	\$0	
41		fascia Board	352	LF	\$0	\$0	
42		Pre-finished Metal Roof Cap	2	EA	\$0	\$0	
43		Flashing @ Condenser/HVAC Equipment Curb	47	LF	\$0	\$0	
44		24x24 Roof Hatch With Telescoping Safety Post - Flashing As Req	1	EA	\$0	\$0	
45		Flashing @ Roof Openings	45	LF	\$0	\$0	
46		Pre-finished Metal Coping	352	LF	\$0	\$0	

PROJECT ID:

Cherokee Country Traffic, K9 & Coroner Facility

SCOPE:

ROOFING

CLIENT'S INFORMATION:

CONTACT:

E-MAIL ADDRESS:

PHONE NUMBER:

Date: 08/17/22

ITEM #	DWG. #	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL COST	TRADE COST
47		Counterflashing @ parapet	352	LF	\$0	\$0	
		Subtotal (Thermal & Moisture Protection)					\$0
SUBTOTAL							\$0.00
OVERHEAD & PROFIT							\$0.00
INSURANCE							\$0.00
CONTINGENCY							\$0.00
TOTAL BASE BID							\$0.00
Note:							

